



MANOHAR PARRIKAR INSTITUTE FOR
DEFENCE STUDIES AND ANALYSES

मनोहर पर्रिकर रक्षा अध्ययन एवं विश्लेषण संस्थान

No 1 Development Enclave, Rao Tula Ram Marg,
Delhi Cantt, New Delhi – 110 010
Ph. No., 26717983 Extn.7315/7206
Email: rktripathi.idsa@nic.in

File No: MPIDSA/SQ/04/2022

Dated: 07th April 2022

**INSTALLATION OF THREE LED DISPLAY PANELS IN BOARD ROOM (Room No. 104,
1st Floor) at MP-IDSA**

Eligibility Criteria:

The bidder must fulfil the following eligibility criteria and should submit the following document:-

1. The bidders should submit the related document in support of the above work issued by any respective departments.
2. The bidders should submit valid PAN No. & GST No.
3. 03 years of audio-visual setup/installation work experience in any of the organization.
4. Before submitting the price bid, the firm shall inspect the site to familiarise with the work required.
5. The work shall be strictly carried out similar as per the scope of work under the supervision of IT cell.
6. The MP-IDSA has the right to reject the quote at any stage without assigning any reason.
7. The quoted rates shall be inclusive of all taxes.
8. The firm shall submit all relevant documents and spot quotation in a sealed envelope by Hand.
9. MP-IDSA shall not be responsible for any injury or loss to any worker of the contractor that may take place while on work. Any compensation or expenditure towards treatment for such injury or loss of the life shall be the sole responsibility of the contractor. The contractor is solely responsible for any damage or injury or accident that may occur to any of his personnel working under his contract. No claim whatsoever arises to MP-IDSA.
10. **Terms of Payment:** Payments shall be made after the successful commissioning & testing of equipment's and items listed at Annexure-II, based on the actual work done, **after deduction of 5% of contract value (without any interest), which shall be kept as performance security against any defect as liability for a period of one year from the date of completion.** During this period if any defect found, the same shall be rectified and replaced immediately by the contractor. No extra payment will be made.

11. Scope of work is given at **Annexure-I**.
12. **Price Bid:** Rates should be quoted item wise as per the enclosed Performa at **Annexure-II**. All rates should be inclusive of GST.
13. Bidders are advised to be present on the scheduled date during opening of the Price Bid.
14. Items to be fitted should be branded or equivalent with comprehensive one year on-site warranty.
15. The contractor shall include cost of supply & transportation of materials, labour, tools, etc. to the site. If any damage occurred during installation of items, which shall be replaced by the firm without any extra cost.
16. **Statutory Deductions:** All the statutory deductions towards GST/TDS etc. shall be made from the bill/s as applicable as per the prevailing rates under the rules. TDS as applicable will be deducted from each bill of the contractor under the statutory rules.
17. **Penalty for Delay:** In case, if the work does not completed within the stipulated time i.e. 07 days after issuing of the work order, Rs.1000/- per day will be deducted towards the final payment.
18. **Liability to Damage:** The contractor will be fully responsible for the damages if any, caused to the assets, property of MP-IDSA by his workers while on duty or otherwise at the institute. The security staff of MP-IDSA will be authorized to search your employees at the time of their leaving the premises after performing their duties. Any damage, loss, theft, burn outs, mishandling of equipment's etc. caused by the contractor's personal to the Institute in whatever form would be recovered from the contractor. The decision of the competent authority shall be final and binding.
19. **Important Dates:**
- | | | | |
|------|---------------------------------------|---|---|
| i. | Publish Date & Time | : | 07 th Apr 2022, 10:00 hrs |
| ii. | On-site Inspection Date & Time | : | upto 11 th Apr 2022, 11:00 hrs |
| iii. | Quotations Submission End Date & Time | : | 12 th Apr 2022, 14:00 hrs |
| iv. | Quotations Opening Date & Time | : | 12 th Apr 2022, 14:30 hrs |


Col. Rajeev Agarwal (Retd.)
Assistant Director (Admin)

SCOPE OF WORK

1. Wall mount installation of 03 LED display panels in Boardroom (Room no. 104, 1st Floor) at MP-IDSA, details are as under:
 - a) 75inch SMART LED TV - 01Nos.
 - b) 43Inch SMART LED TV - 02Nos.
2. All-inclusive Conduiting work, floor cutting and civil & electrical repair work, re-pasting & dry cleaning of carpet, wooden wall panelling, cutting, and repair & polishing as per MP-IDSA satisfaction
3. One Hydraulic Popup Box 6/10 Amp flush mounted power outlet & source connectivity will be installed on the table along with a metal face plate.
4. One 10Amp power outlet each for all three locations of LED TVs including switch socket face plate 2.5sqmmx3 cable to the power console, three pin top on other end and one cable extension.
5. All integration elements including cables connectors, adapters, transceivers and other hardware/software elements of the installed device have to be offered as part of the installation along with the completion of all the equipments listed at **Annexure-II**.
6. The complete work (SITC) should be complete within 07 days after issuing of the work order.
7. The payment will be released after the successful installation, testing and commissioning of equipment's and items listed at **Annexure-II**.
8. The firm should ensure that post installation of the equipment's, the carpet re-pasting and dry cleaning, civil and electrical work in the Room should be restored to its original state.
9. Comprehensive one-year on-site next business day (NBD) warranty with support of both supplied hardware, software (if, any), installation is to be offered.
10. All specifications mentioned are minimum and vendor may quote system with better specifications
11. **All vendors are advised to do a site-survey for passive and active components sizing before quoting.**
12. The installation team will report to the IT team of MP-IDSA during/after of the complete installation of the said work.

Price Bid

Subject: Wall mount installation of 03 led display panels in Boardroom (room no. 104, 1st floor) at MP-IDSA

(Rates Quoted should be inclusive of GST)

S. N.	Description	Qty.	Unit	Rate	Amount
1	Supply of 20Mtr HDMI Cable , Max. Data Rate — 18Gbps. Max. Resolution — 4K@60Hz (4:4:4). Deep Color — Supports 24-bit, 30-bit, 36-bit and 48-bit (RGB or YCbCr) color depths. Best for multimedia applications and surround systems. Multi-Channel Audio Support — Supports audio stream for external decoding by AV receivers and automatic audio syncing capabilities. High Quality Connectors — 24K gold-plated, corrosion-resistant and best possible connectivity. K-Lock Pull-Resistant Connectors — Provides 15lbs of restraining force for a non-slip connection. Shield — Triple overall shield against EMI/RFI interference	2	Nos.		
2	Supply of 15Mtr HDMI Cable , Max. Data Rate — 18Gbps. Max. Resolution — 4K@60Hz (4:4:4). Deep Color — Supports 24-bit, 30-bit, 36-bit and 48-bit (RGB or YCbCr) color depths. Best for multimedia applications and surround systems. Multi-Channel Audio Support — Supports audio stream for external decoding by AV receivers and automatic audio syncing capabilities. High Quality Connectors, corrosion-resistant and best possible connectivity. K-Lock Pull-Resistant Connectors — Provides 15lbs of restraining force for a non-slip connection. Shield — Triple overall shield against EMI/RFI interference	2	Nos.		
3	Supply of 10Mtr HDMI Cable , Max. Data Rate — 18Gbps. Max. Resolution — 4K@60Hz (4:4:4). Deep Color — Supports 24-bit, 30-bit, 36-bit and 48-bit (RGB or YCbCr) color depths. Best for multimedia applications and surround systems. Multi-Channel Audio Support — Supports audio stream for external decoding by AV receivers and automatic audio syncing capabilities. High Quality Connectors, corrosion-resistant and best possible connectivity. K-Lock Pull-Resistant Connectors — Provides 15lbs of restraining force for a non-slip connection. Shield — Triple overall shield against EMI/RFI interference	2	Nos.		
4	Supply of 1.8Mtr HDMI Cable , Max. Data Rate — 18Gbps. Max. Resolution — 4K@60Hz (4:4:4). Deep Color — Supports 24-bit, 30-bit, 36-bit and 48-bit (RGB or YCbCr) color depths. Best for multimedia applications and surround systems. Multi-Channel Audio Support — Supports audio stream for external decoding by AV receivers and automatic audio syncing capabilities. High Quality Connectors, corrosion-resistant and best possible connectivity. K-Lock Pull-Resistant Connectors — Provides 15lbs of restraining force for a non-	1			

	slip connection. Shield — Triple overall shield against EMI/RFI interference				
5	Supply of HDMI Switcher 2X4 HDMI V1.3 Matrix , HDMI 1.3, HDCP 1.1 and DVI 1.0 compliant, Input ports: 2 x HDMI female ports, Output ports: 4 x HDMI female ports Supports digital video formats in Deep Color Mode at up to 36 bits (12bits/ color) and a new lossless compressed (Dolby TrueHD, Dolby Digital Plus and DTS-HD Master Audio) digital audio and LPCM7.1, Supports a wide range of PC and HDTV resolutions from VGA to UXGA and 480i to 1080p	1	Nos.		
6	10Amp Power outlet for all 03 locations including switch socket face plate 2.5sqm x 3 cable to the power console, three pin top on other end, 01 cable extension, including all material and labour	3	Nos.		
7	6/10 Amp Flush Mounted Power Outlet & Source Connectivity Hydraulic Popup Box on Table.	1	Nos.		
8	All other material and labour as per scope of work at Annexure-I	1	Job		
		Grand Total			

Total amount Quoted (in words) Rupees

.....

Note:

1. **The amount quoted should be inclusive of GST.** Conditional Quotes will be rejected.
2. If any discrepancy found in quoting the financial bid in words and figures, the higher quoted amount will be considered.
3. GST & TDS will be deducted as per rules from the quoted amount and may be catered for while quoting the rates.

Signature of the Bidder _____

Name, Address and Telephone No _____

Name of the Agency with Seal _____